Bruhath Benglauru Mahangara Palike, Dasarhalli Zone
Office of the Executive Engineer, Dasarhalli Division.
Schedule - B

Name of the Work :Construction of RCC drains 7th and 9th cross Kalyana Nagara in ward no. 13 Shettyhalli sub division

Sl No	Item Name	Unit	Estimate Quantity	Rate to be Quoted Shrusti Samupadha Construction (Nagesh S)	
				In Figures (Rs)	In Words (Rs)
1	Earthwork excavation by manual means in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods Complete Asper the Directon Of Enggineer -in-charge of the work	CUM	355	175.96	Rupees One Hundred Seventy Five and Ninety Six Paisa Only
2	Removing B S Slab Drain And Stacking Asper the Directon Of Enggineer -in-charge of the work	SQM	479.25	65.72	Rupees Sixty Five and Seventy Two Paisa Only
3	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4.8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing Asper the Directon Of Enggineer -in-charge of the work	CUM	42.29	4443.52	Rupees Four Thousand and Four Hundred Fourty Three and Fifty Two Paisa Only
4	Providing and laying in position plain cement concrete of mix 1:4.8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing Asper the Directon Of Enggineer -in-charge of the work	CUM	10.96	5159.02	Rupees Five Thousand One Hundred Fifty Nine Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner

Sl No	Item Name	Unit	Estimate Quantity	Rate to be Quoted Shrusti Samupadha Construction (Nagesh)	
				In Figures (Rs)	In Words (Rs)
5	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing Asper the Directon Of Enggineer -in-charge of the work	CUM	127.8	5874.52	Rupees Five Thousand Eight hundred and Seventy Four and Fifty Two Only
6	Providing and removing centering, shuttering, strutting,. propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached1 pilasters, buttresses, plinth cilis and string courses cost of all materials, labour Asper the Directon Of Enggineer -in-charge of the work	SQM	1278	310.58	Rupees Three Hundred and Ten and Fifty Eight Paisa Only
7	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery Asper the Directon Of Enggineer -in-charge of the work	Tonne	7.67	64243.42	Rupees Sixty Four Thousand Two Hundred and Fourty Three and Fourty Two Paisa Only
8	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Asper the Directon Of Enggineer -in-charge of the work	SQM	67.5	1680.00	Rupees One Thousand and Six Hundred and Eighy Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner